

**Project: PRJ# 26001 West Robson - Broadwater Road Casing Pipes**

See paragraph 5.3.1 of the Instructions to Tenderers – Part II

All prices and Quotations including the Contract Price shall include all Taxes, but shall not include GST. GST shall be shown separately.

See Form of Agreement Schedule 3 - Supplementary Payment Procedures

**Summary**

Division	Title	Amount
Div 01	General Requirements	
Div 31	Earthwork	
Div 32	Roads and Site Improvements	
Div 33	Utilities	
	Supplemental Costs	
	Tender Price	
	GST	
	Total Tender Price	

Div 01 - General Requirements						Sub Total	\$
Section	Para	Specification Title	Unit	Quantity	Unit Price	Amount	
01 33 01		<b>Project Record Documents</b>					
	1.8.1	Project Record Documents	Lump Sum	1		\$	
01 51 01		<b>Temporary Utilities and Lighting</b>					
	1.6.1	Temporary Utilities and Lighting	Lump Sum	1		\$	
01 52 01		<b>Temporary Structures</b>					
	1.6.1	Temporary Structures	Lump Sum	1		\$	
01 53 01		<b>Temporary Facilities</b>					
	1.9.1	Temporary Facilities	Lump Sum	1		\$	
01 55 00		<b>Traffic Control, Vehicle Access and Parking</b>					
	1.5.1	Traffic Control, Vehicle Access and Parking Monitor & Maintain Casing Backfill Until Paved	Lump Sum	1		\$	
01 57 01		<b>Environmental Protection</b>					
	1.6.1	Environmental Protection	Lump Sum	1		\$	
01 58 01		<b>Project Identification</b>					
	1.3.1	Project Identification	Lump Sum	1		\$	

<b>Div 31 - Earthwork</b>						<b>Sub Total</b>	<b>\$</b>
<i>Section</i>	<i>Para</i>	<i>Specification Title</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Price</i>	<i>Amount</i>	
31 15 60		<b>Dust Control</b>					
	1.5.1	Dust Control	Lump Sum	1		\$	
31 22 16.1		<b>Reshaping Existing Subgrade</b>					
	1.4.2	Reshaping Existing Subgrade	Square Metre	70		\$	
31 23 17		<b>Rock Removal</b>					
	1.6.4	Boulders and Rock Fragments - Provisional No Blasting Permitted	Cubic Metre	10		\$	
31 24 13		<b>Roadway Excavation, Embankment and Compaction</b>					
	1.8.3	Rock Removal To be included under Section 31 23 17	Note				
	1.8.4	Remove Existing Asphalt	Square Metre	70		\$	

<b>Div 32 - Roads and Site Improvements</b>						<b>Sub Total</b>	<b>\$</b>
<i>Section</i>	<i>Para</i>	<i>Specification Title</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Price</i>	<i>Amount</i>	
32 11 16.1		<b>Granular Sub-Base</b>					
	1.4.3	75mm Minus Granular Sub-Base 300mm Thickness for Roads	Square Metres	70		\$	
32 11 23		<b>Granular Base</b>					
	1.4.2	19mm Minus Granular Base 150mm Thickness	Square Metres	70		\$	
32 12 16		<b>Hot-Mix Asphalt Concrete Paving</b>					
	1.5.1, 1.5.2	Asphalt Pavement 50mm Thickness	Square Metres	70		\$	
	1.5.7	Saw Cut Asphalt Pavements	Lineal Metres	30		\$	
32 17 23		<b>Painted Pavement Markings</b>					
	1.5.2	Permanent Painted Pavement Markings	Lump Sum	1		\$	
	1.5.4	Hazard Marker Traffic Control Signs Required Until Repaved	Each	4		\$	

<b>Div 33 - Utilities</b>						<b>Sub Total</b>	<b>\$</b>
<i>Section</i>	<i>Para</i>	<i>Specification Title</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Price</i>	<i>Amount</i>	
33 11 01		<b>Waterworks</b>					
	1.8.2	Payment for watermain includes saw cutting, trench excavation, disposal of surplus excavated material, bedding, supply and installation of all pipe, bolts, gaskets and tie-rods, imported or native backfill as specified, cleaning, pressure and leakage testing, flushing, disinfection and surface restoration under 31 23 01	Note				
	1.8.1, 1.8.2	Watermain Casing Pipe HDPE DR 11 350mm diameter Native Backfill	Lineal Metres	30		\$	

1.8.3	<b>Cap</b> 350mm diameter	Each	4	\$
-------	------------------------------	------	---	----

<b>Supplementals</b>	<b>Sub Total</b>	<b>\$</b>
----------------------	------------------	-----------

Section	Para	Specification Title	Unit	Quantity	Unit Price	Amount
<b>Miscellaneous</b>						
		Mobilization and Demobilization	Lump Sum	1		\$
		Construction Layout and Asbuilt Survey	Lump Sum	1		\$
		Materials Testing	Lump Sum	1		\$

<b>Optional Work</b>	<b>Sub Total</b>	<b>\$</b>
----------------------	------------------	-----------

Section	Para	Specification Title	Unit	Quantity	Unit Price	Amount
<b>Miscellaneous</b>						
		<b>Hydrovac / Daylighting for Utility &amp; Bedrock Locates</b> Up to 3.0m Depth, includes backfill, compaction and all work to restore to existing consitions	Each	5		\$