



Request for Quote

Edgewood, Burton and Rosebery Historical Landfills – Civil Work PRJ26003

ADDENDUM NO. 1

Issued: April 8, 2026

Closing Date: 2:00 pm PDT, April 22, 2026

This Addendum shall be read in conjunction with and considered as an integral part of the Contract Documents; revisions supersede the information contained in the original specifications or previously issued Addendum. Price submitted shall include all items of this Addendum.

By this **Addendum No. 1**, dated April 8, 2026, the Request for Quote documents for PRJ26003: Edgewood, Burton and Rosebery Historical Landfills – Civil Work shall be amended as specified below.

QUESTIONS & ANSWERS:

Q1. We have noted that material can be obtained from the gravel pit adjacent to the Edgewood Landfill. Will MOTT be providing this material for free or should we be contacting them for a price?

A1. MOTT has advised that they don't like competing with local pits/quarries for material but are also unaware of any local sources on the Edgewood side of the ferry. If MOTT is contacted assume that they will charge for the material and those costs should be reflected in the bid.

Q2. Do we include tipping fees for the metal and car hulks?

A2. Yes tipping fees should be included for metal and vehicle hulks taken to transfer stations.

Richmond Steel has advised that they can bale passenger vehicle hulks but not larger hulks (trucks, buses, etc). If larger trucks/buses are found (ie Rosebery) they need to either be cut into pieces or crushed on site with an excavator, or a larger hole dug and the vehicle buried in it. In all cases the vehicles should be assumed to be drained of all fluids. If this assumption is found to be incorrect the RDCK and the Contractor will work to have a vehicle salvage contractor brought in to remove the vehicle for processing at a separate facility.



- Q3. For the Burton Transfer Station, could you please clarify what it is meant to “use equipment to excavate and bury exposed debris in suitable locations”? Are we excavating and relocating buried debris?**
- A3.** Per picture below, an excavator can be brought to site to dig small holes adjacent to exposed debris/rubble, bury the debris/rubble and then cap with 500mm of soil.



Photo 10: Debris found in Southwestern area of site.

Except as modified by Addendum No. 1, the Request for Quote documents for PRJ26003: Edgewood, Burton and Rosebery Historical Landfills – Civil Work shall remain unchanged.

AJ Evenson
Senior Project Manager

- END OF DOCUMENT -