



Request for Quote

Edgewood, Burton and Rosebery Historical Landfills – Civil Work PRJ26003

ADDENDUM NO. 2

Issued: April 13, 2026

Closing Date: 2:00 pm PDT, April 22, 2026

This Addendum shall be read in conjunction with and considered as an integral part of the Contract Documents; revisions supersede the information contained in the original specifications or previously issued Addendum. Price submitted shall include all items of this Addendum.

By this **Addendum No. 2**, the Request for Quote documents for PRJ26003: Edgewood, Burton and Rosebery Historical Landfills – Civil Work shall be amended as specified below.

QUESTIONS & ANSWERS:

- Q1. Burton and Roseberry only allow for 50m3 of fill (supply and install) to cover exposed waste to approx. 500mm, including hand seeding? After viewing the sites, we are concerned that this will not be enough. Do you require all fill for cover to be imported or can we used material on site if we cannot manage with the 50mm allowance. To fill the depressions at Burton may take as much as or more than 200 m3 of cover appropriately.**
- A1. Contractors can use onsite material if they are able to obtain it from within the property where its not part of the historical landfill area. If not enough material is available then it should be imported to the site. The bid form has been updated to increase the qty of material from 50m3 to 200m3 at Burton.
- Q2. In order to access Rosebery and given the narrow and steep grade of the road, we will have to do some road repair(for the top half) and tree trimming. Would this be ok? If so, we will have to blend the costs for this in our schedule of quantities?**
- A2. Yes the tree trimming and road upgrades are acceptable. A line item for the tree limbing and road upgrades has been added to the bid form.

- Q3. Do we need to arrange for a tester to come out and perform a compaction test on the gravel under the lock block wall at Edgewood?**
- A3. Independent testing isn't required as long as the contractor uses a plate compactor, places gravel in suitable lifts and uses water to compact the granular material.

Except as modified by this Addendum and Addendum No. 1 dated April 8, 2026, the Request for Quote documents for PRJ26003: Edgewood, Burton and Rosebery Historical Landfills – Civil Work shall remain unchanged.



AJ Evenson
Senior Project Manager

Attachments: Schedule B – REV1 2026-04-13

- END OF DOCUMENT -

SCHEDULE B: PRICING SCHEDULE – Rev1 2026-04-13

This section shall be read with and shall form part of the Contract Form. The Bidder hereby proposes the following prices to provide all materials, supervision, labour, equipment and all else necessary for the proper supply of the Services. Costs of a general nature that do not pertain to any one item shall be pro-rated among all items. No claim for extra payment on the grounds that the Services supplied could not be properly charged to items within the Description of Services will be considered.

Description	Qty	Unit	Unit price	Extended Price
Edgewood Transfer Station				
Mob/demob equipment to site.	1	ls	\$	\$
Handpick smaller litter in the trees and surrounding area and dispose of in bins.	1	ls	\$	\$
Use equipment to consolidate the metal and tire piles.	1	ls	\$	\$
Use equipment to remove partially buried tires and put in tire pile.	1	ls	\$	\$
Use equipment to remove partially exposed metal and vehicle hulks and place in metal pile.	1	ls	\$	\$
Supply and install locks blocks on edge of slope to prevent waste from being pushed over the edge. Blocks to be installed in an "L" shape approximately 20m long by 10m x 2 high. Including excavation and placement of granular material as per detail.	48	each	\$	\$
Supply and install sufficient fill material to cover exposed waste to approximately 500mm, including hand seeding.	150	m3	\$	\$
Subtotal Edgewood				\$

Description	Qty	Unit	Unit price	Extended Price
Burton Transfer Station				
Mob/demob equipment to site.	1	ls	\$	\$
Handpick smaller litter on southwest side of site and surrounding area and dispose of in bins.	1	ls	\$	\$
Use equipment to remove partially exposed metal and vehicle hulks and place in metal pile.	1	ls	\$	\$
Use equipment to excavate and bury exposed debris in suitable locations.	1	ls	\$	\$
Supply and install sufficient fill material to cover exposed waste to approximately 500mm, including hand seeding.	200	m3	\$	\$
Subtotal Burton				\$

Description	Qty	Unit	Unit price	Extended Price
Rosebery Historical Landfill				
Mob/demob equipment to site.	1	ls	\$	\$
Use equipment to remove partially exposed metal and vehicle hulks and take to closest transfer station or landfill for disposal in metal pile.	1	ls	\$	\$
Use equipment/labour to remove waste on steep exposed slopes and add cover material where necessary.	1	ls	\$	\$
Access Road Upgrades and Tree Limbing	1	ls	\$	\$
Supply and install sufficient fill material to cover exposed waste to approximately 500mm, including hand seeding. Material can be used from on site.	150	m3	\$	\$
Subtotal Rosebery				\$
TOTAL EDGEWOOD, BURTON + ROSEBERY				
GST (5%)				\$
GRAND TOTAL				\$